

Structural Engineering School of Engineering and Technology Postal Address: P.O. Box 4 Klong Luang Pathumthani 12120 Thailand Street Address: Km. 42 Paholyothin Highway Klong Luang Pathumthani 12120 Thailand Tel: 66 (0)2524-6052 Fax: 66 (0)2524-6059 http://www.ait.ac.th

EXECUTIVE SUMMARY

The Structural Engineering and Construction Program, School of Engineering and Technology, Asian Institute of Technology (AIT) was engaged by the Saint-Gobain Weber Co., Ltd. to conduct the performance test of cementitious tile adhesive. The sample in the trademark of "weber.tai flex" was submitted by the Saint-Gobain weber Co., Ltd. The series of test and test methods were detailed in accordance with ISO 13007 / European Norms (EN 12004:2001) as follows:

Specification of cementitious adhesives (C)

Fundamental Characteristics

Characteristic	Requirement	Test Method	Results	
Tensile adhesion strength	≥ 1 N/mm²	ISO 13007 part2 clause 4.4.4.2 or EN1348 § 8.2	PASS	
Tensile adhesion strength after water immersion	≥ 1 N/mm²	ISO 13007 part2 clause 4.4.4.3 or EN1348 § 8.3	PASS	
Tensile adhesion strength after heat aging	≥ 1 N/mm²	ISO 13007 part2 clause 4.4.4.4 or EN1348 § 8.4	PASS	
Open time: tensile adhesion strength	≥ 0.5 N/mm ² after not less than 20min	ISO 13007 part2 clause 4.1or EN 1346	PASS	

Regarding the testing results, it was found that the properties of "weber.tai flex" are conformed to ISO 13007 / European Norms (EN 12004:2001) test methods as specified. These results certify the adequacy and representative character of test samples only.

Reference No: S0588-06

Date of Issue: 14 July 2006

Tested by: SE Lab

Approved by:

(Dr.Sun Sayamipuk) Senior Laboratory Sur





Km. 42 Paholyothin Highway, Klong Luang, Pathumthani, Thailand 12120

P. O. Box 4 Klong Luang, Pathumthani 12120, Thailand. Tel. (66-2) 524-5527, 524-6427 Fax. (66-2) 524-5544

STRUCTURAL ENGINEERING LABORATORY

STRUCTURAL ENGINEERING FIELD OF STUDY

SCHOOL OF ENGINEERING AND TECHNOLOGY

TYPE OF TEST: INITIAL ADHESION STRENGTH (EN 1348:1997)

TEST SPECIMEN: Five (5) specimens of 'weber.tai flex (weber.fermaflex) 'were prepared in the SE laboratory. The mix proportion of water to 'weber.tai flex (weber.fermaflex) 'ratio

was 25 % by weight.

CLIENT: SAINT - GOBAIN WEBER CO., LTD.

DATE OF TEST: July 5, 2006

TEST METHOD: After finish the preparation, the test units were placed in standard conditions for 27 days. Bond the pull head plate to the tile with the high strength epoxy

and keep the test units for a further 24 hour in standard condition. Determine

the tensile adhesive strength.

TEST RESULTS:

Specimen No.	Width of Specimen (mm.)	Length of Specimen (mm.)	Area (mm²)	Maximum Load (N.)	Tensile Adhesion Strength (N/mm²)	Remarks
1	50	50	2,500	4,090	1.64	The failure of all specimens occurred at the interface between
2	50	50	2,500	5,257	2.10	tile adhesive surface and concrete
3	50	50	2,500	5,541	2.22	slab surface.
4	50	50	2,500	4,835	1.93	
5	50	50	2,500	5,090	2.04	
				Average	1.98	

Note: This results certify the adequacy and representative character of the test samples only.

DR. SUN SAYAMIPUK

CHECKED & APPROVED BY :

DR. SUN SAYAMIPUK SENIOR LABORATORY SUPERVISOR July 14, 2006



Km. 42 Paholyothin Highway, Klong Luang, Pathumthani, Thailand 12120

P. O. Box 4 Klong Luang, Pathumthani 12120, Thailand. Tel. (66-2) 524-5527, 524-6427 Fax. (66-2) 524-5544

STRUCTURAL ENGINEERING LABORATORY

STRUCTURAL ENGINEERING FIELD OF STUDY

SCHOOL OF ENGINEERING AND TECHNOLOGY

TYPE OF TEST: ADHESIVE STRENGTH AFTER WATER IMMERSION (EN1348:1997)

TEST SPECIMEN: Five (5) specimens of 'weber tai flex (weber fermaflex) 'were prepared in the SE

laboratory. The mix proportion of water to 'weber.tai flex (weber.fermaflex) 'ratio

was 25 % by weight.

CLIENT: SAINT - GOBAIN WEBER CO., LTD.

July 5, 2006

TEST METHOD: After finish the preparation, the test units were placed in standard conditions for 7 days and stored in water for 20 days. Bond the pull head plate to the tile

with the high strength epoxy and keep the test units for a further 24 hour in

in water at the standard temperature. Determine the tensile adhesive strength.

TEST RESULTS:

DATE OF TEST:

Specimen No.	Width of Specimen (mm.)	Length of Specimen (mm.)	Area (mm²)	Maximum Load (N.)	Tensile Adhesion Strength (N/mm²)	Remarks
1	50	50	2,500	3,717	1.49	The failure of all specimens occurred at the interface between
2	50	50	2,500	3,609	1.44	tile adhesive surface and concrete slab surface.
3	50	50	2,500	3,462	1.38	siab surface.
4	50	50	2,500	3,030	1.21	
5	50	50	2,500	3,884	1.55	
				Average	1.42	

Note: This results certify the adequacy and representative character of the test samples only.

CHECKED & APPROVED BY:

DR. SUN SAYAMIPUK

SENIOR LABORATORY SUPERVISOR July 14, 2006



Km. 42 Paholyothin Highway, Klong Luang, Pathumthani, Thailand 12120

P. O. Box 4 Klong Luang, Pathumthani 12120, Thailand. Tel. (66-2) 524-5527, 524-6427 Fax. (66-2) 524-5544

STRUCTURAL ENGINEERING LABORATORY

STRUCTURAL ENGINEERING FIELD OF STUDY

SCHOOL OF ENGINEERING AND TECHNOLOGY

TYPE OF TEST: ADHESIVE STRENGTH AFTER HEAT AGEING (EN1348:1997)

TEST SPECIMEN: Five (5) specimens of 'weber.tai flex (weber.fermaflex) 'were prepared in the SE

laboratory. The mix proportion of water to 'weber.tai flex (weber.fermaflex) 'ratio

was 25 % by weight.

CLIENT: SAINT - GOBAIN WEBER CO., LTD.

DATE OF TEST: July 5, 2006

TEST METHOD: After finish the preparation, the test units were placed in standard conditions for 14 days and then place in oven for 14 days. Remove from the oven and bond the

pull head plate to the tile with the high strength epoxy. Keep the test units for a

further 24 hour in standard condition. Determine the tensile adhesive strength.

TEST RESULTS:

Specimen No.	Width of Specimen (mm.)	Length of Specimen (mm.)	Area (mm²)	Maximum Load (N.)	Tensile Adhesion Strength (N/mm²)	Remarks
1	50	50	2,500	2,864	1.15	The failure of all specimens occurred at the interface between
2	50	50	2,500	3,197	1.28	tile and tile adhesive surface.
3	50	50	2,500	3,168	1.27	
4	50	50	2,500	3,285	1.31	
5	50	50	2,500	3,491	1.40	
				Average	1.28	

Note: This results certify the adequacy and representative character of the test samples only.

, (

CHECKED & APPROVED BY:

DR. SUN SAYAMIPUK
SENIOR LABORATORY SUPERVISOR
July 14, 2006



Km. 42 Paholyothin Highway, Klong Luang, Pathumthani, Thailand 12120

P. O. Box 4 Klong Luang, Pathumthani 12120, Thailand. Tel. (66-2) 524-5527, 524-6427 Fax. (66-2) 524-5544

STRUCTURAL ENGINEERING LABORATORY

STRUCTURAL ENGINEERING FIELD OF STUDY

SCHOOL OF ENGINEERING AND TECHNOLOGY

TYPE OF TEST: OPEN TIME (EN1346:1997)

TEST SPECIMEN: Fifty (50) specimens of 'weber.tai flex (weber.fermaflex) 'were prepared in the

SE laboratory. The mix proportion of water to 'weber.tai flex (weber.fermaflex) '

ratio was 25 % by weight.

CLIENT: SAINT - GOBAIN WEBER CO., LTD.

DATE OF TEST: July 5, 2006

TEST METHOD: Apply a thin layer of the adhesive to the concrete slab with a straight edge trowel.

After 5, 10, 20 and 30 minutes place the tiles on the adhesive and storage them under standard conditions for 27 days. Bond the pull-head plates to the tiles with the high strength epoxy and keep the test units for a further 24 hour in standard

condition. Determine the tensile adhesive strength.

TEST RESULTS:

Specimen No.	Tensile adhesion strength of specimen in different open time (N/mm²)						
	0 (min.)	5 (min.)	10 (min.)	20 (min.)	30 (min.)		
1	1.61	1.35	1,49	1.80	2.31		
2	1.45	1.57	1.60	2.00	2.10		
2 3	1.53	1.68	1.46	1.84	2.17		
	1.26	1.72	1.78	1.64	2.33		
4 5 6 7	1.77	1.70	1.57	2.13	2.25		
6	1.93	1.91	1.87	2.14	1.82		
7	1.68	1.69	1.84	2.19	2.26		
8	1.71	1.92	1.90	2.27	2.06		
9	1.89	2.04	2.02	2.00	2.30		
10	1.88	1.46	1.98	2.14	2.25		
Average	1.65	1.73	1.73	2.00	2.18		

Note: This results certify the adequacy and representative character of the test samples only.

CHECKED & APPROVED BY

DR. SUN SAYAMIPUK SENIOR LABORATORY SUPERVISOR July 14, 2006